



STRUCTALL BUILDING SYSTEMS

EPS/OSB FOAM CORE ROOF PANELS - METAL SKIN

V:\Projects\14-1745 OSB-Aluminum Skin Span Charts (ICC) Initial Eval\WP2017-04-17.MPS Update\14-1745c OSB-Alum Skin Span Charts (ICC).dwg



1 CLEAR SPAN ISOMETRIC
N.T.S. ISOMETRIC



2 PANEL INTERLOCK DETAIL
N.T.S. DETAIL

GENERAL NOTES (OSB & SHINGLES):

- THIS DESIGN COMPLIES WITH THE STRUCTURAL PROVISIONS OF THE 2012 & 2015 INTERNATIONAL BUILDING CODE & 2012 & 2015 INTERNATIONAL RESIDENTIAL CODE AS WELL AS CURRENT VERSIONS OF THE MN, NC, NJ, NY, OH, SC, VA BUILDING & RESIDENTIAL CODES AS APPLICABLE.
- THIS SHEET CERTIFIES STRUCTURAL DESIGN ONLY (WATERPROOFING BY OTHERS). TOTAL SUPERIMPOSED DEAD LOAD ON ANY PANEL SHALL NOT EXCEED 5 PSF, AND THIS WEIGHT SHALL BE SUBTRACTED FROM THE LIVE LOAD ALLOWABLE VALUES IN THE PANEL ROOF SPAN CHARTS WHEN USING THIS INSTALLATION METHOD.
 - EXAMPLE: IN A 30PSF WIND PRESSURE/SNOW LOAD ZONE, WITH THE ADDITION OF THE MAXIMUM ALLOWABLE 5PSF DEAD LOAD, THE MODIFIED MAXIMUM ALLOWABLE PANEL SPAN SHALL BE GOVERNED BY LOADING CRITERIA OF 35PSF.
- SEAL ALL SEAMS AND CONNECTIONS WITH STRUCTURAL GRADE ADHESIVE SEALANT (1500 PSI MIN. TENSILE LOAD STRENGTH), AND CLEAN ROOF OF ANY DIRT, GREASE, WATER OR OIL.
- ALL FASTENERS TO BE #8 OR GREATER SAE GRADE 5, UNLESS NOTED OTHERWISE. FASTENERS SHALL BE CADMIUM-PLATED OR OTHERWISE CORROSION-RESISTANT MATERIAL AND SHALL COMPLY WITH "SPECIFICATIONS FOR ALUMINUM STRUCTURES" SECTION J.3.1 BY THE ALUMINUM ASSOCIATION, INC., & ANY APPLICABLE FEDERAL, STATE, AND/OR LOCAL CODES.
- THE CONTRACTOR SHALL CAREFULLY CONSIDER POSSIBLE IMPOSING LOADS ON ROOF, INCLUDING BUT NOT LIMITED TO ANY CONCENTRATED LOADS WHICH MAY JUSTIFY GREATER DESIGN CRITERIA. THIS ADDITIONAL ROOF LOAD CRITERIA SHALL BE PROPERLY ANALYZED BY A LICENSED ENGINEER OR REGISTERED ARCHITECT.
- THE CONTRACTOR IS RESPONSIBLE TO INSULATE ALL MEMBERS FROM DISSIMILAR MATERIALS TO PREVENT ELECTROLYSIS.
- PANELS TO BE BY STRUCTALL BUILDING SYSTEMS ONLY. EXCEPT AS EXPRESSLY PROVIDED HEREIN, NO CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
- THIS DETAIL ONLY VALID WHEN SIGNED AND SEALED BY FRANK L. BENNARDO, P.E.
- ENGINEER SEAL AFFIXED HERE TO VALIDATES STRUCTURAL DESIGN AS SHOWN ONLY. USE OF THIS SPECIFICATION BY CONTRACTOR, et. al. INDEMNIFIES & SAVES HARMLESS THIS ENGINEER FOR ALL COST & DAMAGES INCLUDING LEGAL FEES & APPELLATE FEES RESULTING FROM MATERIAL FABRICATION, SYSTEM ERECTION, & CONSTRUCTION PRACTICES BEYOND THAT WHICH IS CALLED FOR BY LOCAL, STATE, & FEDERAL CODES & FROM DEVIATIONS OF THIS PLAN.
- THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
- ** ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

MAXIMUM ALLOWABLE DESIGN PRESSURES:

AS NOTED IN CLEAR SPAN TABLE

DESIGN NOTES:

POSITIVE AND NEGATIVE DESIGN PRESSURES CALCULATED FOR USE WITH THIS SYSTEM SHALL BE DETERMINED BY OTHERS ON A JOB-SPECIFIC BASIS IN ACCORDANCE WITH THE GOVERNING CODE. SITE-SPECIFIC LOAD REQUIREMENTS FOR LIVE LOAD, WIND LOAD, SNOW LOAD OR ANY LOAD COMBINATION SHALL BE DETERMINED IN ACCORDANCE WITH ASCE 7 AND THE 2012 & 2015 INTERNATIONAL BUILDING CODE (AS APPLICABLE) BY SEPARATE ENGINEERING CERTIFICATION AND SHALL BE LESS THAN OR EQUAL TO THE POSITIVE OR NEGATIVE DESIGN PRESSURE CAPACITY VALUES LISTED HEREIN FOR ANY ASSEMBLY AS SHOWN.

GENERAL NOTES:

- THIS SPECIFICATION HAS BEEN DESIGNED AND SHALL BE FABRICATED IN ACCORDANCE WITH THE REQUIREMENTS OF THE 2012 & 2015 INTERNATIONAL BUILDING CODE & 2012 & 2015 INTERNATIONAL RESIDENTIAL CODE AS WELL AS CURRENT VERSIONS OF THE MN, NC, NJ, NY, OH, SC, VA BUILDING & RESIDENTIAL CODES AS APPLICABLE. CONTRACTOR SHALL INVESTIGATE AND CONFORM TO ALL LOCAL BUILDING CODE AMENDMENTS WHICH MAY APPLY. DESIGN CRITERIA BEYOND AS STATED HEREIN MAY REQUIRE ADDITIONAL SITE-SPECIFIC SEALED ENGINEERING. SEISMIC DESIGN HAS NOT BEEN CONSIDERED.
- COMPOSITE ROOF PANELS SHALL COMPLY WITH CHAPTER 7 SECTION 721, CHAPTER 8 SECTION 803, CLASS A INTERIOR FINISH, AND CHAPTER 26 SECTION 2603 OF THE 2012 & 2015 IBC.
- NO 33-1/3% INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS SYSTEM.
- DESIGN PRESSURES AS NOTED HEREIN ARE BASED ON A MAXIMUM TESTED PRESSURE DIVIDED BY A 2.0 FACTOR OF SAFETY.
- THE ARCHITECT/ENGINEER OF RECORD FOR THE PROJECT SUPERSTRUCTURE WITH WHICH THIS DESIGN IS USED SHALL BE RESPONSIBLE FOR THE INTEGRITY OF ALL SUPPORTING SURFACES TO THIS DESIGN WHICH SHALL BE COORDINATED BY THE PERMITTING CONTRACTOR.
- SEPARATE "SITE-SPECIFIC" SEALED ENGINEERING SHALL BE REQUIRED IN ORDER TO DEVIATE FROM LOADS, DEFLECTIONS, OR SPANS CONTAINED HEREIN. LINEAR INTERPOLATION OF THE ALLOWABLE SPAN TABLES LISTED HEREIN SHALL NOT BE PERMITTED. CONTACT THIS ENGINEER FOR ALTERNATE SPAN CALCULATIONS AS MAY BE REQUIRED.
- THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
- THE CONTRACTOR SHALL CAREFULLY CONSIDER POSSIBLE IMPOSING LOADS ON ROOF, INCLUDING BUT NOT LIMITED TO ANY CONCENTRATED LOADS WHICH MAY JUSTIFY GREATER DESIGN CRITERIA. THIS ADDITIONAL ROOF LOAD CRITERIA SHALL BE PROPERLY ANALYZED BY A LICENSED ENGINEER OR REGISTERED ARCHITECT.
- EPS CORE COMPOSITE PANELS SHALL BE CONSTRUCTED USING TYPE 3105-H254 ALUMINUM FACINGS OR ASTM A653, CS, TYPE B HOT DIP GALVANIZED G90 COATED STEEL FACINGS. EXPANDED POLYSTYRENE FOAM SHALL HAVE TYPICAL DENSITY OF 1.0 PCF. THE EPS FOAM SHALL BE ADHERED TO THE ALUMINUM FACING WITH MORAD M640 SERIES ADHESIVE (BY ROHM AND HAAS COMPANY). FABRICATION SHALL BE IN ACCORDANCE WITH APPROVED FABRICATION METHODS BY MANUFACTURER FOR ALL PANELS.
- THE CONTRACTOR IS RESPONSIBLE TO INSULATE ALL MEMBERS FROM DISSIMILAR MATERIALS TO PREVENT ELECTROLYSIS.
- ENGINEER SEAL AFFIXED HERE TO VALIDATES STRUCTURAL DESIGN AS SHOWN ONLY. USE OF THIS SPECIFICATION BY CONTRACTOR, et. al. INDEMNIFIES & SAVES HARMLESS THIS ENGINEER FOR ALL COST & DAMAGES INCLUDING LEGAL FEES & APPELLATE FEES RESULTING FROM MATERIAL FABRICATION, SYSTEM ERECTION, & CONSTRUCTION PRACTICES BEYOND THAT WHICH IS CALLED FOR BY LOCAL, STATE, & FEDERAL CODES & FROM DEVIATIONS OF THIS PLAN.
- EXCEPT AS EXPRESSLY PROVIDED HEREIN, NO ADDITIONAL CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
- ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE THIS CERTIFICATION.

TABLE VALUE DERIVATIONS:

PANEL PROPERTIES:

- PANEL STRUCTURAL PROPERTIES DERIVED FROM CERTIFIED TEST REPORTS Nos. TT-506027B, 506027C, 506027D, 509014A, 509014B BY TERRAPIN TESTING, ESP012351P-1, ESP012351P-2, ESP012351P-3, ESP012351P-3A, ESP012351P-4, ESP012351P-5, ESP012351P-6, EXP012351P-6A, ESP012351P-7, ESP012351P-8, ESP012351P-9, ESP012351P-9A BY ELEMENT MATERIALS TECHNOLOGY.
- PANEL DEAD LOADS HAVE BEEN FACTORED INTO CALCULATIONS FOR LIVE LOADS OR UPLIFT AS WELL AS CALCULATIONS FOR PANEL PROPERTIES.

FRANK L. BENNARDO, P.E.

STATE SEAL
INDICATED BELOW
05/11/2017

VALID FOR (1) JOB(S) ONLY
VALID ONLY WITH RAISED ENGINEER SEAL

FRANK L. BENNARDO, P.E.
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443



STRUCTALL BUILDING SYSTEMS

350 BURBANK ROAD
OLDSMAR, FL 34677
PH: (813) 855-2627

- AL:25555
- DE: 15009, CA 2782
- GA:27525
- IN:10606888
- KS:24215
- LA:30341
- MA:43224
- MD:28152
- MI:49491
- MN:43001
- MO: 2003019621
- MS:16927
- NC:PE027234
- NJ: 24GE04353500
- NY:079356
- OH:66438
- PA:PE060991
- SC:21507
- TX:96064
- VA: 0402 038109
- WI:43753-6

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	RWN	TSB	08/05/14

THIS DOCUMENT IS THE PROPERTY OF FRANK L. BENNARDO, P.E. AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF FRANK L. BENNARDO, P.E. * ALTERATIONS, ADDITIONS, HIGHLIGHTING, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

COPYRIGHT FRANK L. BENNARDO P.E.

14-1745

SCALE:
PAGE DESCRIPTION:

1

OF 2

MAXIMUM ALLOWABLE CLEAR SPAN TABLE:

Live Load &/or Uplift w/ 5/8" Max OSB	Deflection Limit (L/...)	3" Panels		4" Panels			6" Panels		
		0.024" Alum Skin	0.030" Alum Skin	0.024" Alum Skin	0.030" Alum Skin	26ga Steel Skin	0.024" Alum Skin	0.030" Alum Skin	26ga Steel Skin
		1-LB EPS	1-LB EPS	1-LB EPS	1-LB EPS	1-LB EPS	1-LB EPS	1-LB EPS	1-LB EPS
+/- 13 psf	120	12'-12"	16'-0"	15'-4"	17'-3"	16'-6"	18'-1"	20'-2"	20'-5"
+/- 13 psf	180	11'-4"	15'-1"	13'-5"	15'-1"	16'-2"	16'-7"	18'-8"	19'-11"
+/- 13 psf	240	10'-4"	13'-9"	12'-2"	13'-9"	14'-8"	15'-1"	16'-12"	18'-1"
+/- 18 psf	120	11'-9"	13'-11"	13'-11"	15'-3"	14'-4"	15'-8"	17'-6"	17'-8"
+/- 18 psf	180	10'-4"	13'-9"	12'-2"	13'-9"	14'-4"	15'-1"	16'-12"	17'-8"
+/- 18 psf	240	9'-4"	12'-6"	11'-1"	12'-6"	13'-4"	13'-9"	15'-5"	16'-6"
+/- 23 psf	120	10'-11"	12'-5"	12'-9"	13'-8"	12'-10"	14'-0"	15'-8"	15'-10"
+/- 23 psf	180	9'-7"	12'-5"	11'-3"	12'-9"	12'-10"	14'-0"	15'-8"	15'-10"
+/- 23 psf	240	8'-8"	11'-7"	10'-3"	11'-7"	12'-5"	12'-9"	14'-4"	15'-3"
+/- 28 psf	120	10'-0"	11'-4"	11'-8"	12'-6"	11'-8"	12'-9"	14'-3"	14'-5"
+/- 28 psf	180	8'-12"	11'-4"	10'-7"	11'-12"	11'-8"	12'-9"	14'-3"	14'-5"
+/- 28 psf	240	8'-2"	10'-11"	9'-8"	10'-11"	11'-8"	11'-12"	13'-6"	14'-5"
+/- 33 psf	120	9'-3"	10'-6"	10'-9"	11'-7"	10'-10"	11'-10"	13'-3"	13'-4"
+/- 33 psf	180	8'-7"	10'-6"	10'-1"	11'-5"	10'-10"	11'-10"	13'-3"	13'-4"
+/- 33 psf	240	7'-9"	10'-4"	9'-2"	10'-4"	10'-10"	11'-5"	12'-9"	13'-4"
+/- 37 psf	120	8'-10"	9'-11"	10'-3"	10'-11"	10'-3"	11'-3"	12'-6"	12'-8"
+/- 37 psf	180	8'-3"	9'-11"	9'-9"	10'-11"	10'-3"	11'-3"	12'-6"	12'-8"
+/- 37 psf	240	7'-6"	9'-11"	8'-10"	9'-12"	10'-3"	10'-12"	12'-4"	12'-8"
+/- 43 psf	120	8'-2"	9'-3"	9'-6"	10'-2"	9'-6"	10'-5"	11'-8"	11'-9"
+/- 43 psf	180	7'-10"	9'-3"	9'-3"	10'-2"	9'-6"	10'-5"	11'-8"	11'-9"
+/- 43 psf	240	7'-2"	9'-3"	8'-5"	9'-6"	9'-6"	10'-5"	11'-8"	11'-9"
+/- 48 psf	120			9'-0"	9'-8"	9'-1"	9'-11"	11'-1"	11'-2"
+/- 48 psf	180			8'-12"	9'-8"	9'-1"	9'-11"	11'-1"	11'-2"
+/- 48 psf	240			8'-2"	9'-2"	9'-1"	9'-11"	11'-1"	11'-2"
+/- 53 psf	120			8'-7"	9'-3"	8'-7"	9'-5"	10'-7"	10'-8"
+/- 53 psf	180			8'-7"	9'-3"	8'-7"	9'-5"	10'-7"	10'-8"
+/- 53 psf	240			7'-11"	8'-11"	8'-7"	9'-5"	10'-7"	10'-8"
+/- 58 psf	120			8'-3"	8'-10"	8'-3"	9'-0"	10'-1"	10'-2"
+/- 58 psf	180			8'-3"	8'-10"	8'-3"	9'-0"	10'-1"	10'-2"
+/- 58 psf	240			7'-8"	8'-8"	8'-3"	9'-0"	10'-1"	10'-2"
+/- 63 psf	120			7'-10"	7'-10"	7'-11"	8'-8"	9'-8"	9'-10"
+/- 63 psf	180			7'-10"	7'-10"	7'-11"	8'-8"	9'-8"	9'-10"
+/- 63 psf	240			7'-6"	7'-6"	7'-11"	8'-8"	9'-8"	9'-10"
+/- 68 psf	120			7'-3"	7'-3"	7'-8"	8'-4"	9'-4"	9'-5"
+/- 68 psf	180			7'-3"	7'-3"	7'-8"	8'-4"	9'-4"	9'-5"
+/- 68 psf	240			7'-3"	7'-3"	7'-8"	8'-4"	9'-4"	9'-5"
+/- 76 psf	120					7'-3"	7'-11"	8'-10"	8'-11"
+/- 76 psf	180					7'-3"	7'-11"	8'-10"	8'-11"
+/- 76 psf	240					7'-3"	7'-11"	8'-10"	8'-11"
+/- 78 psf	120						8'-9"	8'-10"	
+/- 78 psf	180						8'-9"	8'-10"	
+/- 78 psf	240						8'-9"	8'-10"	
+/- 83 psf	120						8'-6"	8'-7"	
+/- 83 psf	180						8'-6"	8'-7"	
+/- 83 psf	240						8'-6"	8'-7"	
+/- 88 psf	120						8'-3"	8'-4"	
+/- 88 psf	180						8'-3"	8'-4"	
+/- 88 psf	240						8'-3"	8'-4"	
+/- 93 psf	120						8'-0"	8'-1"	
+/- 93 psf	180						8'-0"	8'-1"	
+/- 93 psf	240						8'-0"	8'-1"	

*OSB SELF WEIGHT NOT TO EXCEED 2.08 PSF. 7/16" OSB CAN BE USED IN LIEU OF 5/8" OSB IF DESIRED

OTHER CONSIDERATIONS:

- FRONT OVERHANG MAY BE UP TO 3'-0" WITH VALUES LISTED HEREIN. MAXIMUM UNSUPPORTED SIDE OVERHANG IS 25% OF LAST PANEL WIDTH (i.e. 12" MAX FOR 48" PANEL WIDTH).
- ROOF PITCH NOT TO EXCEED 3:12


CLEAR SPAN TABLE USE INSTRUCTIONS:

- DETERMINE TYPE OF ENCLOSURE TO BE COVERED (OPEN, SCREENED WALLS, OR FULLY ENCLOSED).
- VERIFY APPROPRIATE DESIGN LOAD WITH GOVERNING MUNICIPALITY AND BUILDING CODES IN EFFECT FOR THE PROJECT LOCATION USING 2012 & 2015 INTERNATIONAL BUILDING CODE (AS APPLICABLE) AS PROVIDED BY SEPARATE ENGINEERING, BY A LICENSED ENGINEER OR REGISTERED ARCHITECT. SEPARATE ENGINEERING MAY BE REQUIRED FOR ALTERNATE DESIGN LOADS.
- FIND ALLOWABLE COMPOSITE PANEL CLEAR SPAN IN TABLES FOR APPROPRIATE PANEL DEPTH, FACING THICKNESS, AND EPS CORE DENSITY SELECTED.
- INDICATES VALUES NOT VALID FOR USE.

DEFLECTION NOTES:

- (RECOMMENDED, VERIFY WITH LOCAL JURISDICTION)
- USE L/120 FOR ALL MEMBERS SUPPORTING ROOFS OVER AN OPEN OR SCREEN-WALLED ROOM.
 - USE L/180 FOR ALL MEMBERS SUPPORTING ROOFS WITH A NON-PLASTERED CEILING OVER AN ENCLOSED ROOM.
 - USE L/240 FOR ALL MEMBERS SUPPORTING ROOFS WITH A PLASTERED CEILING OVER AN ENCLOSED ROOM

MECHANICAL APPLICATION OF OSB AND SHINGLES TO EPS PANEL



SHINGLE NOTES: (APPLICABLE TO THIS DETAIL ONLY)

SHINGLES MUST HAVE 0.65 OR GREATER SOLAR REFLECTANCE AS RATED BY SHINGLE MANUFACTURER.

STARTER ROWS OF SHINGLES SHALL HAVE TWO LINES AT MID TAB AREA. SHINGLE ROW INSTALLED WITH TABS FACING IN THE UPWARD DIRECTION OF THE ROOF SLOPE.

SUBSEQUENT ROWS OF SHINGLES INSTALLED WITH THE TABS FACING IN THE DOWNWARD DIRECTION OF THE ROOF SLOPE WITH ONE LINE OF ADHESIVE UNDER THE SHINGLE AT MID COVERED AREA.

FRANK L. BENNARDO, P.E.

STATE SEAL
INDICATED BELOW
05/11/2017

VALID FOR (1) JOB(S) ONLY
VALID ONLY WITH RAISED ENGINEER SEAL

FRANK L. BENNARDO, P.E.
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 FAX: (954) 354-0443
POWERED BY THE INNOVATIONS OF
EX ENGINEERING
EXPERIENCE MORE AT ENGINEERINGEXPRESS.COM

STRUCTURAL BUILDING SYSTEMS

- 350 BURBANK ROAD
OLDSMAR, FL 34677
PH: (813) 855-2627
- AL:25555
 - DE:15009, CA 2782
 - GA:27525
 - IN:10606888
 - KS:24215
 - LA:30341
 - MA:43224
 - MD:28152
 - MI:49491
 - MN:43001
 - MO:2003019621
 - MS:16927
 - NC:PE027234
 - NJ:24GE04353500
 - NY:079356
 - OH:66438
 - PA:PE060991
 - SC:21507
 - TX:96064
 - VA:0402 038109
 - WI:43753-6

DRWN	CHKD	DATE
FRWN	TSB	08/05/14

REMARKS
INITIALS

THIS DOCUMENT IS THE PROPERTY OF FRANK L. BENNARDO, P.E. AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF FRANK L. BENNARDO, P.E. *ALTERATIONS, ADDITIONS, HIGHLIGHTING OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

COPYRIGHT FRANK L. BENNARDO P.E.

14-1745

SCALE:

PAGE DESCRIPTION:

V:\Projects\14-1745 OSB-Aluminum Skin Span Charts (ICC)\Initial Eval\WP2017-04-17.MPS Update\14-1745c OSB-Alum Skin Span Charts (ICC).dwg 05/11/2017 - 4:06pm lermuser